BILL TO STORE 00745 JIMMY CARTER BLVD.

ITEM NO.	QUANTITY	DESCRIPTION OF EQUIPMENT	APPROVED MANUFACTURER	MECHANICAL												ITEM NO.	REMARKS (ALL ITEMS BY CHICK-FIL-A UNLESS OTHERWISE NOTED)
				ELECTRICAL						PLUMBING							
				VOLT	PH	KW	AMP	HP	NEMA RATING	HW	CW	FW	FW2	IW	ROUGH-IN		
550	1	DOUBLE WARMING DRAWER	TOASTMASTER MODEL #3880A	120	1	1.00	8.3		5-15P							550	
560	1	FRY HOLDING STATION	BKI MODEL #FW-15BB	120	1	1.84	15.4		5-20P							560	ON ITEM #105; (1) BILL TO EQUIPMENT REPLACEMENT TEAM
563D	1	SANDWICH SLIDE	BKI MODEL #2TSM-2624R	120	1	1.09	9.13		5-20P							563D	6' CORD & PLUG - PLACED ON ITEM #105
563S	1	SANDWICH SLIDE	BKI MODEL #SM-2624L	120	1	.548	4.56		5-20P							563S	6' CORD & PLUG - PLACED ON ITEM #105
564	1	PRODUCT HOLDING CABINET	DUKE MODEL #FWM3-24CF6-120	120	1	1.6	13.3		5-15P							564	LOCATED IN ITEM #120b - FRANKE TABLE CIRCUIT #7 & #14
565C	1	FOOD COOKER/WARMER	ROUNDUP MODEL #CW-100	120	1	1.5	12.5		L5-15P							565C	PROVIDE WITH TWIST LOCK PLUG-ORDER WITH (1) 3VOL042, (2) 3VOL043, (8) 3VOL051, AND (8) 3VOL061
580	1	MULTI-USE HOLDING CABINET	DUKE MODEL #MUHC-52-120	120	1	2.88	24		L5-30P							580	PROVIDED WITH TWIST LOCK PLUG
581	1	DUMP CART	FRANKE: CTS CART #18008028													581	
581R	1	DUMP CART	EQUIPMENT TO BE REUSED/RELOCATED													581R	
600R	1	MIXER	EQUIPMENT TO BE REUSED/RELOCATED	VERIFY	VER		VERIFY	VER	VERIFY							600R	ELECTRICIAN TO CHANGE PLUG TO TWIST LOCK IF NEEDED - FIELD VERIFY
600aR	1	MIXER ROLLING CART	EQUIPMENT TO BE REUSED/RELOCATED													600aR	
606	1	JUICER WORK STATION	INTERMETRO													606	WITH (2) SOLID SHELVES AND 27-1/2" LEGS - ORDER (2) 2436FS, (4) 27PK3
607	1	COUNTER TOP LEMON JUICER	SUNKIST MODEL #J-1	115	1			.25	5-15P							607	LOCATED ON ITEM #606
610	1	FOOD PREP TABLE	EAGLE MODEL #T2424STE-BS													610	WITH BACKSPLASH - ORDER WITH 1-5/8" DIAMETER LEGS
645	1	FOOD PREP TABLE	EAGLE MODEL #T3054STEM-BS													645	WITH BACKSPLASH AND MARINE EDGE - ORDER ON 5" CASTERS
647	1	SALAD TABLE	EAGLE MODEL #T3066STEM-BS													647	WITH BACKSPLASH AND MARINE EDGE - ORDER ON 5" CASTERS
651	1	LOCKERS	WINHOLT MODEL #WL-612													651	2 TIERS, 12 OPENINGS
653	2	ERGONOMIC WORK STOOL - 5 BLADE	GLOBAL MODEL #571005													653	
655R	2	FILE CABINET	EQUIPMENT TO BE REUSED/RELOCATED													655R	
656	1	DESK CHAIR	HON MODEL #7901AB10T													656	
660	3	PAPER TOWEL DISPENSER	SAN JAMAR MODEL #T1490TBK													660	REFER TO ARCHITECTURAL SHEETS FOR DETAILS ON MOUNTING HEIGHTS AND LOCATIONS
661	1	MOP RACK														661	FURNISHED BY OWNER
669R	1	OFFICE SAFE	EQUIPMENT TO BE REUSED/RELOCATED	VERIFY	VER				VERIFY							669R	INSTALL SAFE AS PER MANUFACTURER'S WRITTEN INSTRUCTIONS
671	13	FLAT-VU MENU BOX	C3 LIGHTING SOLUTIONS SIZE B	120	1	.054	.45		5-20P							671	VERIFY MENU BOARD LAYOUT
701	1	CONDIMENT RACK	INTERMETRO - 24"x48" GEN3 GRID + BINS													701	ORDER (1) H210C, (24) SB91055CAS, (2) SB91587CAS
712	4	DUNNAGE RACK (22"x36")	INTERMETRO MODEL #HP2236PDMB													712	
723HW	2	WIF FLOOR SHELF UNIT (7' POST, 18"x42")	INTERMETRO													723HW	METROSEAL III - (5) 1842NK3, (4) 86PK3, (4) 9993S
724H	1	FLOOR SHELF UNIT (7' POST, 18"x48")	INTERMETRO													724H	METROSEAL III - 3 SHELVES ABOVE DUNNAGE SHELF, 1 SHELF BELOW DUNNAGE SHELF
724HW	1	WIF FLOOR SHELF UNIT (7' POST, 18"x48")	INTERMETRO													724HW	METROSEAL III - (5) 1848NK3, (4) 86PK3, (4) 9993S
730	1	FLOOR SHELF UNIT (6' POST, 24"x24")	INTERMETRO													730	METROSEAL III - 2 SHELVES ABOVE DUNNAGE SHELF, 1 SHELF BELOW DUNNAGE SHELF
731H	1	FLOOR SHELF UNIT (7' POST, 24"x30")	INTERMETRO													731H	METROSEAL III - 3 SHELVES ABOVE DUNNAGE SHELF, 1 SHELF BELOW DUNNAGE SHELF
732D	1	36" DRYING RACK	INTERMETRO - DRYING RACK UNIT													732D	(4) MX74P, (2) MX2436G, (2) M4F2436, (2) RPMX36-CBEAM, (2) DR36S, (1) MTR2436XE
732H	3	FLOOR SHELF UNIT (7' POST, 24"x36")	INTERMETRO													732H	METROSEAL III - 3 SHELVES ABOVE DUNNAGE SHELF, 1 SHELF BELOW DUNNAGE SHELF
732HT	1	FLOOR SHELF UNIT (7' POST, 24"x36")	INTERMETRO													732HT	METROSEAL III - 3 SHELVES ABOVE DUNNAGE SHELF, 1 SHELF BELOW DUNNAGE SHELF; (1) DD9514
733H	1	FLOOR SHELF UNIT (7' POST, 24"x42")	INTERMETRO													733H	METROSEAL III - 5 SHELVES
734H	7	FLOOR SHELF UNIT (7' POST, 24"x48")	INTERMETRO													734H	METROSEAL III - 3 SHELVES ABOVE DUNNAGE SHELF, 1 SHELF BELOW DUNNAGE SHELF
736H	1	FLOOR SHELF UNIT (7' POST, 24"x60")	INTERMETRO													736H	METROSEAL III - 3 SHELVES ABOVE DUNNAGE SHELF, 1 SHELF BELOW DUNNAGE SHELF
741U	2	GEN3 KIT (UTILITY)	INTERMETRO													741U	(1) 24"x48" SHELF + GEN3 COMPONENTS, (1) 48" GRID + UTILITY ACCESSORIES - SEE INTERIOR ELEVATIONS FOR MOUNTING INFO.
741V	1	GEN3 KIT (VEGGIE PREP)	INTERMETRO													741V	(1) 24"x48" SHELF + GEN3 COMPONENTS, (1) 48" GRID + VEGGIE PREP ACCESSORIES - SEE INTERIOR ELEVATIONS FOR MOUNTING INFO.
748	1	BREADING OVERSHELF UNIT (7' POST)	INTERMETRO													748	METROSEAL III - (1) 24"X72" WIRE SHELF, (1) 14"X72" SOLID SHELF, (3) 8"X14" DIVIDERS, & (3) SNAKE FRAMES
748a	1	STAINLESS STEEL BACK PANEL	ATLANTA CUSTOM FABRICATORS (60"X72" W/HEMMED EDGES)													748a	MOUNTED ON #748 WITH HEMMED EDGE FACING AWAY FROM BREADING TABLE
751I	1	GEN3 INVERTED SHELF KIT (14"x30")	INTERMETRO													751I	(1) 24X30 SHELF, (1) 56" TRACK, (2) 12" UPRIGHTS, (2) INVERTED BRACKETS - SEE INTERIOR ELEVATIONS FOR MOUNTING INFORMATION
752I	1	GEN3 INVERTED SHELF KIT (14"x30")	INTERMETRO													752I	(1) 24X36 SHELF, (1) 56" TRACK, (2) 12" UPRIGHTS, (2) INVERTED BRACKETS - SEE INTERIOR ELEVATIONS FOR MOUNTING INFORMATION
773	1	GEN3 SHELF (18"x42")	INTERMETRO													773	SEE INTERIOR ELEVATIONS FOR MOUNTING INFORMATION
774	3	GEN3 SHELF (18"x48")	INTERMETRO													774	SEE INTERIOR ELEVATIONS FOR MOUNTING INFORMATION
774F	1	GEN3 SOLID SHELF (18"x48")	INTERMETRO													774F	SOLID SHELF - SEE INTERIOR ELEVATIONS FOR MOUNTING INFORMATION
774S	3	SUSPENDED SHELF (18"x48")	INTERMETRO													774S	METROSEAL III - SEE STRUCTURAL SHEETS FOR INSTALLATION INFORMATION
774Sa	9	VERTICAL SHELF DIVIDER (8" HIGH X 18" DEEP)	INTERMETRO MODEL #DD18K3													774Sa	MOUNTED ON 12" CENTERS AT FOOD PREP AREA - NOT SHOWN ON PLAN
774Sb	2	FLAT PLEXIGLASS PANEL	CUSTOM FABRICATION (48"x70"x1/4")													774Sb	MOUNTED TO ALUMINUM ANGLE BETWEEN #794S AND #774S AT SALAD PREP AREA
776S	3	SUSPENDED SHELF (18"x60")	INTERMETRO													776S	METROSEAL III - SEE STRUCTURAL SHEETS FOR INSTALLATION INFORMATION
776Sa	12	VERTICAL SHELF DIVIDER (8" HIGH X 18" DEEP)	INTERMETRO MODEL #DD18K3													776Sa	MOUNTED ON 12" CENTERS AT FOOD PREP AREA - NOT SHOWN ON PLAN
780	1	GEN3 SHELF (24"x24")	INTERMETRO													780	METROSEAL III - SEE INTERIOR ELEVATIONS FOR MOUNTING INFORMATION
781	1	GEN3 SHELF (24"x30")	INTERMETRO													781	METROSEAL III - SEE INTERIOR ELEVATIONS FOR MOUNTING INFORMATION
781I	1	GEN3 INVERTED SHELF KIT (24"x30")	INTERMETRO													781I	(1) 24X30 SHELF, (1) 56" TRACK, (2) 12" UPRIGHTS, (2) INVERTED BRACKETS - SEE INTERIOR ELEVATIONS FOR MOUNTING INFORMATION
782	1	GEN3 SHELF (24"x36")	INTERMETRO													782	METROSEAL III - SEE INTERIOR ELEVATIONS FOR MOUNTING INFORMATION
783	1	GEN3 SHELF (24"x42")	INTERMETRO													783	SEE INTERIOR ELEVATIONS FOR MOUNTING INFORMATION
784	4	GEN3 SHELF (24"x48")	INTERMETRO													784	SEE INTERIOR ELEVATIONS FOR MOUNTING INFORMATION
784I	1	GEN3 INVERTED SHELF KIT (24"x48")	INTERMETRO													784I	(1) 24X48 SHELF, (1) 56" TRACK, (2) 12" UPRIGHTS, (2) INVERTED BRACKETS - SEE INTERIOR ELEVATIONS FOR MOUNTING INFORMATION
785	1	GEN3 SHELF (24"x54")	INTERMETRO													785	SEE INTERIOR ELEVATIONS FOR MOUNTING INFORMATION
792S	2	SUSPENDED SHELF (30"x36")	INTERMETRO													792S	METROSEAL III - SEE STRUCTURAL SHEETS FOR INSTALLATION INFORMATION
794S	8	SUSPENDED SHELF (30"x48")	INTERMETRO													794S	METROSEAL III - SEE STRUCTURAL SHEETS FOR INSTALLATION INFORMATION
796S	6	SUSPENDED SHELF (30"x60")	INTERMETRO													796S	METROSEAL III - SEE STRUCTURAL SHEETS FOR INSTALLATION INFORMATION

FOR BID ONLY
FOR BID ONLY
FOR BID ONLY
FOR BID ONLY

Chick-fil-A
5200 Buffington Rd.
Atlanta Georgia,
30349-2998

Revisions:

Mark	Date	By

Seal

TriMark
Foodservice Equipment, Supplies and Design
STRATEGIC

3011 Industrial Parkway East
Knoxville, Tennessee 37921
Phone (865) 637-2525
Fax (865) 522-4448

STORE# 00745

5455 Jimmy
Carter Blvd.
Norcross, GA
30093-1512

SHEET TITLE
EQUIPMENT
SCHEDULE

DWG EDITION S97-100
REVISION 00

Job No. :
Store : #00745
Date : 01-19-18
Drawn By : CdL
Checked By: THW

Sheet
K2.2